958

SANITARY DIVISION.

Dated 1st May 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Sanitary Division, up to 15th June 1918, for providing Sanitary conveniences to Public Office Buildings, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of October 1918.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for providing sanitary conveniences to Public Office Buildings, Bangalore," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Materials required for providing sanitary conveniences to the Public Office Buildings, Bangalore.

No.	Items	Per	Quantity
	(1) Council and Secretary's Chambers.		
1	Doulton's white queensware large area closet with raised decorations and metalls keramic joint, 3 gallons paisely cistern with enamelled cast iron cover, etc., as per Doulton's Catalogue, page No. 15, Pattern No. 838.	Each	5
2	Doulton's Improved Lavatories page 247, pattern No. 1103, as per Doulton's Catalogue.	"	5
3	Doulton's angle Urinals, page 342, pattern No. 19, as per Doulton's Catalogue...	"	5
4	4" Cast Iron Bends of 100 degrees	"	7
5	Do soil pipe	R. ft.	245
6	4"×4" cast iron single junction pipe 100 degrees	Each	4
7	4"×4" double junction pipe 100 degrees	"	2
8	2½" cast iron pipe	R. ft.	245
9	6" square milk white tiles	No.	1,000
10	Do Marchalies tiles	"	1,000
11	Galvanised wrought iron tank (4×4×4)	Each	1
12	Drain cleaning cane rods containing 100 rods of 3 feet each with looking arrangements, cleaning accessories 4"×6" brushes 2,.....scrapers 2 squirels 2, etc.	Set	1
	(2) Two wings, east and west.		
1	Doulton's white queensware large area closets with paisely cistern and polished brass pipe, page 14, pattern No. 837 as per Doulton's Catalogue.....	Each	8
2	Doulton's Improved Lavatories as per Doulton's Catalogue, page 240, Pattern No. 432A. Warcely pattern.	"	8
3	Doulton's urinal ranges of 3 with lipped basins as per Doulton's Catalogue, page 348, Pattern No. 20.	"	4
4	Doulton's urinals improved circular backed "Vulcan" range of 3 circular backed urinals with backs and brasses in one piece jambs, etc., galvanised cast iron automatic touch and pointed cast iron brackets as per Doulton's Catalogue, page 340, Pattern No. 763.	"	4
5	4" cast iron soil pipe	R. ft.	250
6	3" do	"	250
7	4" cast iron bends 100 degrees	Each	20
8	4"×4" singie junction pipes 100 degrees	"	16
9	3" cast iron bends 100 degrees	"	12
10	4"×4" double junction pipes 100 degrees	"	4
11	2½" Nahni traps	"	24
12	6" square milk white tiles	No.	4,000
13	6" Flooring Marchalies tiles	"	4,000
14	Galvanised wrought iron tank (4×4×4) with 1½" ball valve arrangements ...	Each	2
15	2" Galvanised wrought iron pipes	R. ft.	150
16	1½" Do	"	300
17	1" Do	"	500
18	¾" Do	"	500
19	2" Galvanised cock	No.	1
20	1½" Do	"	2
21	1" Do	"	12
22	¾" Do	"	12
23	½" Do	"	24
24	4" Lead pipes	R. ft.	50
25	3" Do	"	100
26	1½" Do	"	100
27	¾" Do	"	200
28	½" Do	"	300

No.	Items	Per	Quantity
29	Steel ferrot drain cleaner $1\frac{1}{2}$" diameter of 3' long	No.	2
30	Do 1" do	"	2
31	Do $\frac{3}{4}$" do	"	2
32	Do $\frac{1}{2}$" do	"	2
33	Do $\frac{1}{8}$" do	"	2
	(3) *Constructing underground combined latrine and urinals.*		
1	Doulton's white queensware large area closet with paisely cistern polished brass pipe No. 837 as per Doulton's Catalogue.	Each	1
2	Doulton's Improved Hindustani closet. Page No. 333 as per Richardson and Cruddas Catalogue on Sanitary fittings.	"	2
3	Doulton's single person circular backed urinals, etc., No. 739, page 344, as per Doulton's Catalogue.	"	4
4	4" cast iron bends of 100 degrees	"	1
5	Do soil pipe	R. ft.	30
6	4"×4" cast iron single junction pipe 100 degrees	Each	1
	(4) *Laying stoneware pipes outside connections up to Sampige tank.*		
1	7" stoneware pipes	R. ft.	6,430
2	Cast iron manwhole cover and frame	Each	37
3	Do steps	"	74
4	Field flushing apparatus 4" diameter	"	4
5	4"×4" stone sewer trap	"	8
6	Wrought iron ventilating shaft 4" diameter 20' length	"	1

N. SUBBA RAO,
Offg. Executive Engineer.

MYSORE DIVISION.

Notice.

The attention of the public is invited to advertisement in detail published in *Mysore Gazette*, dated 25th April 1918, calling for tenders for constructing Village Elementary Boys' School at Haradanahalli in Chamrajnagar Taluk.

P. SUBBA RAO,
For *Executive Engineer.*

KOLAR DIVISION.

Dated 27th April 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 16th May 1918, for extending the District Office building at Kolar to provide accommodation to the District Economic Superintendent at Kolar. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1918.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for extending the District Office building at Kolar to provide accommodation to the District Economic Superintendent at Kolar," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.